KADUR DIVISION.

Dated 14th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th January 1930, for construction of Quarters for Revenue Sub-Division Officer at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. to 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and twenty-five only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for construction of Quarters for the Revenue Sub-Division Officer at Chikmagalur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

10. Percentage rates either below the estimated amount or lowest tendered amount, will not be accepted.

11. In all matters of dispute regarding quality of work, and rates the decision of the Chief Engineer is final and legally binding.

Approximate quantities for constructing Revenue Sub-Division Officers' Quarters at Chikmagalur.

Serial No.	Item of work	Per	Quantity	Rates	
				In figures	In words
1	Earthwork excavating foundation and filling in basement.	C.yd.	193		
2	Stone jelly concrete in motor ...	C.ft.	1,309		
3	Burnt stone in mud including bond stones	,,	4,352		
4	Burnt brick in clay	,,	4,198		
5	Burnt brick in motar	,,	1,182		
6	Burnt stone slabs 6" thick dressed and put up.	S.ft.	325		
7	Cut stone pillars 9' high 9" square with base and capitals well dressed and edges chamferred, etc., complete.	Number	4		
8	Cut stone pillars 7' high 6" square with base and capital, etc., complete.	,,	4		
9	Teakwood pannelled door with double shutters, with iron fittings clamps, etc., complete.	S.ft.	129		
10	Teakwood battened door including iron fittings, etc., complete.	,,	232		
11	Teakwood windows single side shutters half battened and ½ glazed in 4 halves and fixed inside with iron bars complete.	,,	216		
12	Teakwood glazed ventilators with iron bars complete.	,,	23		
13	Teakwood wall shelves with battened shutters and cross planks.	,,	52		
14	Teakwood work wrought and put up including wood oiling and tarring.	C.ft.	218·45		

Serial No.	Item of work	Per	Quantity	Rates	
				In figures	In words
15	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete.	Square	35·00		
16	Kidge tiles set in mortar	R.ft.	248		
17	Teakwood eave boards plain	,,	418		
18	Plastering with chunam ...	Sqr.	102		
19	White washing two coats	,,	102		
20	Coping with burnt brick in mortar and plastering with chunam.	R.ft.	75		
21	Teakwood planking for valleys including zinc sheets.	,,	75		
22	Flooring with Mangalore tiles over 3" concrete bed and cement pointing.	Sqr.	13·14		
23	Silicate painting..	,,	16·56		
24	Flooring with Kaddapah slabs on 3" concrete bed and cement pointing.	,,	5·20		
25	Cement pointing...	,,	7·00		
26	Providing iron pipes to draw off water from all rooms.	R.ft.	18		
27	Providing sinks in kitchen and bath rooms	Number	4		
28	Providing mortar and pestle stones ..	,,	2		
29	Moulding around doors and windows ...	Lump	sum		
30	Providing pendents	Number	16		
31	Consturcting parapet wall and carnice over the bay in front of office rooms.	Lump	sum		
32	Constructing drains to lead off water ...	Lump	sum		
33	Gravelling open yard for 2 yards wide alround the buildings.	Lump	sum		
34	Providing wooden railings	Lump	sum		
35	Providing date and name board ...	Lump	sum		
36	Clearing site and levelling ground ...	Lump	sum		
37	Suddry and unforeseen works ...	Lump	sum		

Dated 14th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Execuive Engineer, Kadur Division, up to 17th January 1930, till 3 P.M. for construction of Quarter s for the Amildar at Tarikere. An approximate estimate of quantities is given below. The se quantiesare not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineers Office at Chikmagalur between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the from given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Quarters for the Amildar at Tarikere" in defalt of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Shimoga Circle, Shimoga who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

10. Percentage rates either below the estimated amount or lowest tendered amount will not be accepted.

11. In all matters of dispute regarding quality of work and rates, the deceision of the Chief Engineer, is final and legally binding.

Approximate quantities for constructing Amildars' Quarters at Tarikere.

Sl. No	Item of work	Per	Quantity	Rates In figures and in words
1	Earthwork excavating foundation and filling in basement.	Cyd.	191	
2	Stone jelly concrete in mortar	C.ft.	1,253	
3	Burnt stone in mud including bond stones ...	,,	4,226	
4	Burnt brick in clay	,,	3,448	
5	Burnt brick in mortar	,,	1,250	
6	Burnt stone slabs 6″ thick dressed and put up ...	S.ft.	332	
7	Cut stone pillars 9′ high 9″ square with base and capitals well dressed and edges chemferred, etc., complete.	No.	4	
8	Cut stone pillars 7′ high 5″ square with base and capital, etc., complete.	,,	4	
9	Teakwood pannelled door with double shutters, with iron fittings clamps, etc., complete.	S.ft.	71	
10	Teakwood battened door including iron fittings, etc., complete.	,,	269	
11	Teakwood windows single side shutters half battened and ½ glazed in 4 halves and fixed inside with iron bars complete.	,,	178	
12	Teakwood glazed ventilators with iron bars complete.	,,	54	
13	Teakwood wall shelves with battened shutters and cross planks.	,,	36	
14	Teakwood work wrought and put up including wood oiling and tarring.	C.ft.	207·78	
15	Roofing with First Class Mangalore tiles on teak reepers, etc., complete.	Sqr.	33·75	
16	Ridge tiles set in mortar	R.ft.	244	
17	Teakwood eave boards plain	,,	410	
18	Plastering with chunam	Sqr.	90·00	
19	White washing two coats	,,	90·00	
20	Coping with burnt brick in mortar and plastering with chunam.	R.ft.	76	
21	Teakwood planking for valleys including zinc sheets.	,,	41	
22	Flooring with Mangalore Tiles over 3″ concrete bed and cement pointing.	Sqr.	12·20	
23	Silicate painting	,,	13·00	
24	Flooring with Kaddapah slabs on 3″ concrete bed and cement pointing.	,,	4·55	
25	Cement pointing	,,	6·50	
26	Providing iron pipes to draw off water from all-rooms.	R.ft.	18	
27	Providing sinks in kitchen and bath rooms ...	No.	4	
28	Providing mortar and pestle stones	,,	2	
29	Moulding around doors and windows	Lump sum		
30	Providing pendents	No.	6	
31	Constructing parapet wall and carnise over the bay in front of office rooms.	Lump sum		
32	Constructing drains to lead off water	Do		
33	Gravelling open yard for 2 yards wide alround the buildings.	Do		
34	Providing wooden railings	Do		
35	Providing date and name board	Do		
36	Clearing site and levelling ground	Do		
37	Sundry and unforeseen works	Do		

Abstract Notification, dated 9th December 1929.

The attention of public is invited to the notice calling for tenders for constructi Bridge across Hemavati near Banakal published on page 1443 of Part VI of *Mysore Gazet* dated 12th December 1929. Last date for receiving tenders is 23rd December 1929 3 P.M.

L. A. H. WINCKLER,
Executive Engine